



Your Roofing Company  
 123 Sample Street  
 Yourtown, State 12345

Prepared By: Bob Ford  
 (877) 697-2673  
 your@email.com

## Supplemental Claim

<b>DATE</b>	10/16/2019
<b>ESTIMATE #</b>	E2019-38114
<b>STRUCTURES</b>	1

1000 Opportunity Way, Denver, CO 80202

Roof			
ITEM NAME	QTY	PRICE	AMOUNT
Remove Tear off, haul and dispose of comp. shingles - 3 tab	43.53 SQ	\$49.92	\$2,173.02
Remove Add. layer of comp. shingles, remove & disp. - 3 tab	43.53 SQ	\$31.78	\$1,383.38
Remove Laminated - comp. shingle rfg. - w/ felt Per Colorado State Law all Roofers must carry Roofing Workers Compensation & General Liability Insurance. Please see attached documentation. Original Loss Draft Sheet paid for DMO rates. All demolition is done by RFG, Roofers are doing all demolition.	43.53 SQ	\$51.31	\$2,233.52
Add. layer of comp. shingles, remove & disp. - Laminated	43.53 SQ	\$39.04	\$1,699.41
Tear off T-Lock Shingle Heavy weight shingle with 20% labor increase	43.53 SQ	\$69.00	\$3,003.57
Remove Additional charge for high roof (2 stories or greater)	38.08 SQ	\$0.00	\$0.00
Laminated - comp. shingle rfg. - w/out felt	47.88 SQ	\$277.43	\$13,283.35
Additional charge for high roof (2 stories or greater)	41.89 SQ	\$0.00	\$0.00
Roofing felt - 15 lb.	43.53 SQ	\$36.54	\$1,590.59
Double Felt 15 Lb For low slope roofing Code requirement	1.8 SQ	\$36.54	\$65.77
Aluminum rake / gable edge trim - color finish Replacement of the "powder coated" roofing metal existing on the eaves and rakes	468.39 LF	\$7.45	\$3,489.51
ice and water barrier Section 1507.2.8.2 "In areas where there has been a history of ice forming along the eaves causing a backup of water, an ice barrier that consists of at least two layers of underlayment cemented together or of a self-adhering polymer modified bitumen sheet shall be used in lieu of normal underlayment and extend from the lowest edges of the roof surfaces to the point at least 24 inches inside the exterior wall line of the building" As per manufacturers installation specifications. Please see attached documents. Two rows of ice and water barrier required	1410.91 SF	\$1.82	\$2,567.86
Roof Metal - Step Flashing	142.29 LF	\$8.20	\$1,166.78
Asphalt Ridge - Standard Profile As per attached manufacturers specifications	275.55 LF	\$6.68	\$1,840.67
Asphalt Starter As per attached manufacturers specifications	468.39 LF	\$2.20	\$1,030.46
Detach & Reset Gutters	330.03 LF	\$4.89	\$1,613.85

Tarpping and Protecting Landscape Perimeter * 5 ft (tarp width) * \$0.68. Per EPA all homes built prior to 1978 must be tarped 5' around perimeter and tarp must be disposed.	468.39 LF	\$3.40	\$1,592.53
Roof Metal - Headwall Flashing	6.74 STK	\$6.21	\$41.86
Valley Metal R905.2.8.2 Valleys. Valley linings shall be installed in accordance with the manufacturer's instructions before applying shingles. Valley linings of the following types shall be permitted: 1. For open valleys (valley lining exposed) lined with metal, the valley lining shall be not less than 24 inches (610 mm) wide and of any of the corrosion-resistant metals in Table R905.2.8.2. 2. For open valleys, valley lining of two plies of mineral-surfaced roll roofing, complying with ASTM D 3909 or ASTM D 6380 Class M, shall be permitted. The bottom layer shall be 18 inches (457 mm) and the top layer not less than 36 inches (914 mm) wide. 3. For closed valleys (valley covered with shingles), valley lining of one ply of smooth roll roofing complying with ASTM D 6380 and not less than 36 inches wide (914 mm) or valley lining as described in Item 1 or 2 shall be permitted. Self-adhering polymer modified bitumen underlayment complying with ASTM D 1970 shall be permitted in lieu of the lining material.	43.18 LF	\$5.91	\$255.19

Flat Roof			
ITEM NAME	QTY	PRICE	AMOUNT
Tear off, hail and dispose of modified bitumen roofing	1.1 SQ	\$48.72	\$53.59
Asphalt Roof - Modified Bitumen Modified bitumen comes in rolls of 2 SQ, and has to be rounded up to the nearest value of 2 Modified bitumen cannot be returned to supplier and extra material cannot be reused	1.21 SQ	\$410.55	\$496.77

Labor Base Charge			
ITEM NAME	QTY	PRICE	AMOUNT
Rofer - General Laborer - per hour Re-nail of the decking	43.53 SQ	\$139.00	\$6,050.67

**Notes:**

---

<b>Subtotal</b>	<b>\$45,632.33</b>
<b>TOTAL</b>	<b>\$45,632.33</b>